


Cite this: *RSC Adv.*, 2019, 9, 32278

Motion of droplets into hydrophobic parallel plates

Xiongheng Bian,^{ID} Haibo Huang* and Liguao Chen*

Due to the superior operability and good anti-interference, the prospect of controlling microdroplets using a parallel plate structure (PPS) is very promising. However, in practical applications, droplets in such structures are often affected by various factors, resulting in deformation, evaporation, stress rupture and other phenomena, leading to equipment failure. Therefore, how to simply and effectively transfer liquid droplets to PPS to maintain the stable and efficient operation of the system has become an urgent problem to be solved. In this paper, a simple and effective ratchet-like strategy (relaxing and squeezing actions) is introduced to transfer droplets. To analyze the mechanism of the strategy and optimize the control, we conduct this study from three aspects. First, the droplet movement trend is obtained by analyzing the pressure between SPS and PPS. Second, the reasons why the droplet can achieve this inward motion are investigated. Through theoretical analysis, which is also proven by simulations and experiments, we creatively put forward that the asymmetric change of the contact angle (CA) induced by the asymmetric structure is the fundamental cause of this kind of motion. Due to the asymmetric change of the contact angle, the CA in the PPS will reach the advancing angle first in the squeezing process, and the CA in the SPS will reach the receding angle first in the relaxing process, thus causing the inward movement of the droplet. Third, to optimize this strategy, the effects of the following governing parameters are researched individually based on the corresponding simulations and experiments: the control parameters (the initial gap width of the PPS H_0 and the amount of squeezing and relaxing of ΔH) and the thickness of the top plate. Subsequently, an optimized ratchet-like cycle is achieved. In summary, these findings not only provide a new method by which to realize the movement of droplets toward hydrophobic PPSs but also creatively point out the cause of the ratchet strategy, which can be applied in many microfluidics fields.

Received 6th July 2019
Accepted 16th September 2019

DOI: 10.1039/c9ra05135j

rsc.li/rsc-advances

1. Introduction

In recent years, the control of droplet motion has been extensively discussed as one of the most important fluid control strategies. Various droplet driving methods have been thoroughly studied,¹ among which the most common methods include surface temperature changes, surface chemical properties,^{2–4} hydrophilic and hydrophobic surface structures,^{5–7} electric field application,^{8–11} acidic and alkaline (pH) environments,¹² mechanical vibration,^{13–18} *etc.* Droplet operation is widely used in microfluidic chips,^{19–21} integrated circuits,²² industrial experimental equipment,²³ liquid collection²⁴ and other fields. Hydrophobic parallel plate structure (PPS) is widely used in various applications due to its good maneuverability and good anti-interference. As is known, although there are many ways to realize the unidirectional movement of liquid droplets, there are few ways to realize the transport of droplets into a hydrophobic PPS. Generally, an electrowetting force is always used to achieve

this. However, this method often requires high voltages,^{25,26} which can damage microfluidics chips and has an effect on biochemical substances in the droplets. A novel concise method is needed to solve this problem; thus, the ratchet-like strategy is first introduced.

It is well known that droplets on wetting gradient surfaces can move along the design direction, and repeated squeeze-release droplets can reduce the hysteresis caused by contact angle hysteresis (CAH).²⁷ In previous studies, the ratchet mechanism has mainly been applied to uniform structures (SPS, PPS or non-parallel plate structures). The case of nonparallel plates has been most extensively studied. According to research,^{28,29} droplets sandwiched between two non-parallel plates with a hydrophilic surface were observed to move toward the tip due to relaxing and squeezing the droplets. This phenomenon has been speculated to be mainly caused by the asymmetric depinning (AD) of droplets, which means that the trailing edge remains pinned as the leading edge advances during the squeezing process and that the leading edge remains pinned as the trailing edge recedes during the relaxing process.^{28,30–33} Later research found that the droplet is transported not only by the AD but also by symmetric depinning (SD), which means that both the leading

Robotics & Microsystem Center, Collaborative Innovation Center of Suzhou Nano Science and Technology, Soochow University, Suzhou 215123, China. E-mail: hbhuang@suda.edu.cn; chenliguo@suda.edu.cn



and trailing edges are advancing or receding.³¹ In fact, the efficiency of the SD model is much lower than that of the AD model. If the SD model is included in the transport process, the movement efficiency of the liquid bridge will be reduced.³⁰ Ataei *et al.*^{30,38} optimized the ratchet parameters to achieve a more efficient ratchet cycle by decreasing the SD model. Wang *et al.*³⁴ demonstrated that hydrophobic saw-tooth plates could improve the transport efficiency substantially by obstructing the inefficient SD model. In addition to the uniform structure, Huang *et al.*³¹ proposed a parallel-nonparallel (P-NP) combinative structure for immersion lithography; however, it cannot be used in hydrophobic situations. How to transport droplets from an SPS into a PPS, which can be widely used in microfluidics applications, has not been investigated.

In this paper, a ratchet-like strategy is introduced to move a droplet into hydrophobic parallel plates. First, we demonstrate the process of the droplets entering the hydrophobic PPS using a squeezing and relaxing (ratchet-like) strategy. Second, the pressure on the droplet pinned between the PPS and SPS is analyzed and simulated in detail. On this basis, the reason why the droplet can enter the PPS through the ratchet-like strategy is given theoretically and verified by experiments and simulations. Finally, the control parameters are analyzed and optimized, and a good performance is obtained, which is verified by simulations and experiments.

2. A novel strategy to move droplets into hydrophobic PPS

This novel strategy was shown in Fig. 1. The entire control system was placed horizontally, with the top and bottom plates parallel to each other. Droplets were placed between the SPS and PPS. The upper and lower interfaces of the SPS and PPS were hydrophobic. The boundary of the liquid droplet in the PPS was called the leading edge, and the boundary in the SPS was called the trailing edge. The initial contact angle (CA) was similar to the advancing contact angle (α_a). Meanwhile, the top plate was placed over the bottom plate with a set initial gap width (H_{\max}). The bottom plate was moved horizontally toward the top plate at a low speed (0.05 mm s^{-1}); therefore, the droplet was considered quasi-static. As soon as the top plate touched the droplet, the bottom plate movement was stopped immediately (Fig. 1a). Then, a liquid bridge was formed between the PPS and SPS (Fig. 1b). Subsequently, a slow downward movement of the top plate was carried out (0.4 mm s^{-1}) to squeeze the bridge for a distance of ΔH (Fig. 1b and c), and then the liquid bridge was relaxed the same amount (Fig. 1c and d). Afterward, the droplet could move toward this hydrophobic PPS. The midpoint of the leading and trailing edges (point O in Fig. 1b) was used as the reference point to measure the distance of the liquid bridge movement in the horizontal direction. This liquid bridge movement was marked as ΔX (as in Fig. 1d), and the direction toward the PPS was recognized as positive.




Fig. 1 (a) Initial position of the droplet before bridge formation. (b) Initial position of the liquid bridge after bridge formation. The gap width is represented by H_{\max} . (c) The bridge is squeezed for ΔH , and the gap width is represented by H_{\min} . (d) Subsequently, the squeezed liquid bridge was relaxed for ΔH to H_{\max} to finish the ratchet-like cycle.

3. Analysis of the pressure applied on the droplets pinned between the SPS and PPS

We first analyzed the pressure on the droplets pinned between the PPS and SPS. As shown in Fig. 2a, the variables on the profile are defined, and H and α are the width of the gap and the CA in the PPS, respectively. The intersections of the leading edge with the top and bottom plate are labeled b_1 and a_1 , respectively, and those of the trailing edge with the top and bottom plate are labeled b_2 and a_2 , respectively. o_2 represents the intersection point between the top plate side surface and the bottom plate interface, and o_1 represents the intersection point between the vertical extension line of the top plate side surface and the bottom plate, which also divides the bottom plate into two SPS and PPS zones. L_a represents the length of the droplet in the PPS, L_b represents the length of the droplet in the SPS (o_1a_2), and L_c represents the length of the droplet on the plate (o_2b_2). θ and β represent the wetting angles between the droplet and the top plate side surface and the bottom interface of the SPS,






Fig. 2 (a) Schematic diagram of the droplet pinned between the SPS and PPS. (b) Simulations to determine exactly how the pressure difference (ΔP) is affected by various parameters (α_a , θ_a and H).

respectively. Then, the pressure in the PPS, which is labeled P_{w1} , can be written as follows:

$$P_{w1} = \gamma \left[\frac{2 \sin(\alpha - \frac{\pi}{2})}{H} + \frac{1}{R_{l1}} \right] + P_a \quad (1)$$

Similarly, the surface tension of the SPS, which is labeled P_{w2} , can be calculated by the following formula:

$$\begin{aligned} P_{w2} &= \gamma \left[\frac{-\cos \theta + \sin \beta}{L_b} + \frac{1}{R_{l2}} \right] + P_a \\ &= \gamma \left[\frac{\sin \theta - \cos \beta}{H + L_c} + \frac{1}{R_{l2}} \right] + P_a \end{aligned} \quad (2)$$

where P_a is the atmospheric pressure and R_{l1} and R_{l2} are the horizontal curvatures of the pinned droplet in the PPS and SPS, respectively. Therefore, the pressure difference between the PPS and SPS ($\Delta P = P_{w2} - P_{w1}$) can be represented as:

$$\begin{aligned} \Delta P &\approx \gamma \left[\frac{-\cos \theta + \sin \beta}{L_b} + \frac{1}{R_{l2}} + \frac{2 \cos \alpha}{H} - \frac{1}{R_{l1}} \right] \\ &= \gamma \left[\frac{\sin \theta - \cos \beta}{H + L_c} + \frac{1}{R_{l2}} + \frac{2 \cos \alpha}{H} - \frac{1}{R_{l1}} \right] \end{aligned} \quad (3)$$

From the equation, we find that when the droplets are on the hydrophobic surface ($\alpha > 90^\circ$), α and ΔP are negatively correlated—the smaller is α , the greater is ΔP . H is positively correlated to ΔP ; thus, the larger is H , the larger is ΔP . However, because of the coupling of θ and β and their correlation with L_b and L_c , it is difficult to analyze the relationship between θ , β and ΔP directly. Therefore, the such relationships were also studied based on the simulation results.

3.1 Analysis of the Laplace pressure based on simulations

Without considering CAH ($\alpha_a = \alpha_r$, $\theta_a = \theta_r$), we discussed the influence of α_a , θ_a and H through simulations. During the simulations, the volume of the droplet is set to 0.69 μL . Since

the gap width is related to the volume of the droplet, to calculate the minimum gap width, the parameter ($\sqrt[3]{V}$) is multiplied. The results are shown in Fig. 2b, in which the curves represent the situation when $\Delta P = 0$. The upper and lower parts of the curves indicate that the droplets tend to move inward or outward, respectively. The pressure difference is related to the vertical range between the actual parameters and the relevant curves. For example, if the actual experimental parameters are $\alpha_a = 100^\circ$, $\theta_a = 90^\circ$ and $H = 0.6$ mm (point A), then the corresponding point on the curve is point B. Therefore, ΔP is positively related to the length of segment AB. According to these results, three conclusions can be drawn. First, a larger gap width is beneficial to droplet inward motion. Second, for a constant α_a , a larger θ_a promotes inward motion (a bigger ΔP). But as θ_a increases, the change rate of the gap width (H) versus θ_a curves decreases, which illustrates the weaker influence of θ_a on ΔP . Third, contrary to the effect of θ_a , as α_a increases, a larger gap width is needed to achieve inward motion, which also means that a larger α_a hinders the inward motion.

3.2 Hysteresis force induced by CAH

The influence of CAH on droplet motion is mainly reflected by the influence of CA in eqn (1) and (2). Because of CAH, contact angles α , θ and β are no longer fixed values but are ranges of quantities, i.e., $\alpha, \beta \in (\alpha_r, \alpha_a)$ and $\theta \in (\theta_r, \theta_a)$, which are the reasons why CAH hinders the inward motion. For example, when $\alpha = \alpha_a = 100^\circ$, the droplet tends to move inward, that is to say, $P_{w1} < P_{w2}$ without considering CAH. But due to the function of CAH, although α is still close to α_a (P_{w1} remains roughly the same), β can be smaller than α_a , and θ can also be smaller than θ_a . Therefore, according to eqn (2), P_{w2} can be smaller. If P_{w2} is no longer larger than P_{w1} , then there won't be inward motion. From this result, it can be found that a larger CAH (α_{CAH} and θ_{CAH}) can cause a larger hysteresis force to hinder the motion into the PPS.



4. Analysis of droplet transport into the PPS by the ratchet-like strategy

4.1 Experiment and simulation fundamentals

4.1.1 Experiment fundamentals. In the following experiments, glass was chosen as the plate material, and the surfaces were cleaned ultrasonically for 10 minutes. Subsequently, the upper surface of the bottom plate and the lower surface of the top plate were treated with hydrophobic materials. Upon placing droplets on different surfaces, we recorded and measured their actual contact angles using a CCD camera. The first type of material was Teflon-AF1600 (DuPont). The receding and advancing contact angles of the Teflon-coated sample were approximately 99° and 119° , respectively, with an error of 3° . The other type was hydrophobic-treated SiO_2 , which had an advancing angle of 100° and a receding angle of 80° , with an error of 3° . The receding and advancing contact angles of the nontreated sample were approximately 45° and 75° , respectively, with an error of 3° . The motion of the top plate was precisely controlled and located using a micro-motion platform. To ensure that the droplet was in the quasi-static state, the movement speed was set to 0.4 mm s^{-1} . To better observe the droplet motion process, a red background light was added in the experiment, and a charge coupled device (CCD) camera was used to record this process. Deionized water was used as the experimental object in the experiment. The experiments were repeated four times, and similar results were obtained. The capillary number $\text{Ca} = \mu u / \gamma$ (the velocity is small) and the bond number $\text{Bo} = g \rho L^2 / \gamma$ (in scale of 10^{-2}) were small. Here, γ is the surface tension coefficient and L was the characteristic length. Therefore, the entire process was treated as quasi-static, and the influence of gravity on the whole process was neglected. In addition, since the experimental process was transitory, and the effect of droplet evaporation was also neglected.

4.1.2 Simulation fundamental. In this paper, an improved model based on Surface Evolver is used to simulate the motion of a droplet from the SPS into the hydrophobic PPS. Surface Evolver is a simulation software used to research fluid stability under the influence of surface tension and other energy and various constraints.³⁵ In previous research, a simulation of droplets pinned between the SPS and PPS has been studied by Berthier,²⁵ but there are still two shortcomings in the analysis. First, the effect of the side surface was ignored. Second, the impact of CAH on the equilibrium state was not taken into account. To address the first problem, a hydrophilic side surface is added to the model, which coincides with the practical application. To solve the second problem, an approach proposed by Santos and White³⁶ is adopted to implement CAH. This approach is achieved by adding a force of friction (the magnitude of which depends on the CAH). In this way, it can be ensured that the contact line only moves when the contact angle is beyond the advancing angle (α_a) or below the receding angle (α_r).

4.1.3 Simulation process. Overall, the whole simulation process has two periods. The first is bridge formation, and the other is motion based on the ratchet-like strategy. In this paper,

we pay more attention to the second period, but fundamental information about the bridge forming period is also provided here. Bridge forming (Fig. 3a and b): When the droplet on the bottom plate touched the side surface of the top plate, the liquid expanded into the PPS with α_a (by capillary force), wetted along the side surface with θ_a , and receded in the SPS with α_r . Therefore, the CAs on the bottom surface in the PPS approached α_a , while those on the bottom surface in the SPS were close to α_r . Ratchet-like motion (Fig. 3b–d): After the equilibrium state was achieved, the top plate was vertically moved to squeeze the bridge step by step in intervals of 0.001 mm . In each step, the bridge shape was reformed with the change of the gap width. After the squeezing process, a similar relaxing process was carried out *via* moving upward step by step in 0.001 mm increments. Simulations were performed using surfaces with different material parameters and control parameters one by one. It's worth emphasizing that the experimental and simulation results were consistent (as shown in Fig. 5–7 and 9).

4.2 Process of moving the droplet into the PPS by ratchet-like strategy

From the above experiment, we found that two necessary and sufficient conditions must be satisfied if this inward motion is to be achieved. (1) In the process of relaxing, the tailing edge must first reach the receding angle. (2) In the process of squeezing, the leading edge must first achieve the advancing angle. Based on these two requirements, we have carried on the analysis below.




Fig. 3 Simulation process of the formation of a liquid bridge and the squeezing and relaxing actions of droplets. (a) Initial state of the droplet before the simulation. (b) Simulation diagram after the formation of the liquid bridge. (c) Simulation diagram after squeezing the liquid bridge. (d) Simulation diagram after relaxing the liquid bridge.






Fig. 4 (a) Schematic diagram of the initial state before relaxing. (b) Instantaneous analysis diagram of the contact angles during the relaxing process. (c) Overall relaxing and squeezing process analysis of contact angles α and β .




Fig. 5 First and second ratchet cycle used to illustrate the ratchet-like process. (a) Leading and trailing edges (b) the CAs on the bottom surface versus the ratchet-moving process in the first ratchet cycle. (c) Leading and trailing edges. (d) The CAs on the bottom surface versus the ratchet-moving process in the second ratchet cycle.






Fig. 6 Motion of the bridge with the ratchet process under the reference conditions but with three different values of H_0 at 0.4 mm, 0.5 mm and 0.6 mm; thus, the results are from both simulations and experiments.

4.2.1 Analysis of the first requirement. First, we define the parameters of the droplets during relaxing action. The parameters in Fig. 4a are consistent with the previous definition. Fig. 4a is the state before the relaxing process. Fig. 4b is the pinned period during the relaxing process. In this figure, the intersection points of the leading edge with the top and bottom plates are b'_1 and a'_1 , and the intersection points of the trailing edge with the top and bottom plates are b'_2 and a'_2 . c_1 in Fig. 4b also indicates the point labelled b_2 in Fig. 4a, so we get $a'_2c_1 = a_2b_2$. Point c_2 in Fig. 4b is the intersection point between the extension line of a'_2c_1 and the dashed circle (equal curvature circle). The chord $a'_1b'_1$ is marked as chord 1, and the chord a'_2c_2

is marked as chord 2. We assume that $H = H_0 + \Delta H$. Here, H_0 is the initial width of the gap, and ΔH is the rising distance of the top plate. Because the pressure in the droplet is negatively correlated with the width of the gap and the radius of curvature R , $\Delta H \propto R$, we can assume that $R = R_0 + m\Delta H$, where m is the parameter decided by the droplet movement process and R_0 is the initial radius of curvature in the droplet.

Then, we can compare the relationship between α and β during the relaxing process. According to Fig. 4b, it can be found that $\alpha = \frac{\pi}{2} + \arcsin(L_{CH1}/2R)$ and $\beta = \angle c_1a'_2a'_1 + \arcsin(L_{CH2}/2R)$. Since $\angle c_1a'_2a'_1$ is a constant value, the comparison between the change rate of α and β is really the comparison between $L_{CH1}/2R$ and $L_{CH2}/2R$. The values of $L_{CH1}/2R$ and $L_{CH2}/2R$ can be calculated as:

$$L_{CH1}/2R = (L_{CH1}^0 + \Delta H)/(R_0 + m\Delta H) = (L_{CH1}^0 + \Delta H)/(R_0 + m\Delta H) \quad (4)$$

$$L_{CH2}/2R = \sin \left[\arcsin \left(\sqrt{d^2 + L_b^2} / 2R \right) + \arctan \left[\frac{L_b}{H_0 + L_C} \right] - \arctan \left(\frac{L_b}{d} \right) \right] = (L_{CH2}^0 + n\Delta H)/(R_0 + m\Delta H) \quad (5)$$

where n is a parameter indicating the change rate of L_{CH2} and $d = H_0 + L_C + \Delta H$. L_{CH1}^0 and L_{CH2}^0 are the initial lengths of chord 1 and chord 2, and H_0 is the initial width of the gap. Since the rate of change of R is much greater than the rate of change of ΔH , $m \gg 1$. Then, $L_{CH1}/2R \approx L_{CH1}^0/(R_0 + m\Delta H)$ and $L_{CH2}/2R \approx L_{CH2}^0/(R_0 + m\Delta H)$. So, we can get:

$$\frac{d\beta}{dH} \approx \frac{L_{CH2}^0}{L_{CH1}^0} \frac{d\alpha}{dH} \quad (6)$$




Fig. 7 Motion of the bridge with the ratchet process under the reference conditions but with three different ΔH at 0.1 mm, 0.2 mm, 0.3 mm and 0.4 mm. The results are from simulations and experiments.






Fig. 8 Simulation of the value of ΔX versus $|\Delta H|$ for the same situation as shown in Fig. 3 but with three different values of H_{up} at 0.2 mm, 0.3 mm and no limit.

Therefore, since $L_{CH2}^0 > L_{CH1}^0$ (according Fig. 4a), the change rate of β with ΔH is larger than the change rate of α with ΔH . In addition, since the initial value of β is smaller than α , during the relaxation process, β is always smaller than α . In other words, the first requirement can be satisfied.

4.2.2 Analysis of the second requirement. Afterward, the relationship between contact angles α and β during the squeezing process was also analysed. Compared to the relaxing process, the parameters L_a , L_b are changed (L_a increase, L_b decrease), but L_c maintains a similar value (sliding along the side surface is not considered here). According to eqn (4), L_a has little effect on the value of L_{CH1} , which means that the change

rate of α during relaxing and squeezing processes is similar. Conversely, according to eqn (5), the smaller is L_b , the smaller are change rates of the term $\arcsin(\sqrt{d^2 + L_b^2}/2R)$ and the term $\arctan[L_b/(H_0 + L_c)] - \arctan(L_b/d)$, the smaller is the change rate of the length of chord 2, and the smaller is the change rate of contact angle β . Thus, it can be seen that the change of contact angle β during the squeezing process is slower than that in the relaxing process. Therefore, compared with β rapidly reaching the receding angle during the relaxing process, it is much more difficult for β to reach the advancing angle. This leads to satisfaction of the third requirement.

4.2.3 Overall process analysis. By combining the above analyses, we obtain a schematic diagram of the changes of the contact angles during the whole relaxing and squeezing process, as shown in Fig. 4c. The red line is the prediction line of CA α , the green line is the prediction line of CA β , and the blue line is the theoretical curve of the width of the gap. (a)–(c) is the relaxing process, and (c)–(e) is the squeezing process. First, in the process of (a) and (b), β approaches α_r faster than α . Second, in the process of (b) and (c), the receding movement occurs first in SPS, and due to this displacement, the α reduction also slows. Third, in the process of (c) and (d), compared with the relaxing process, the change rate of α is the same, but the change rate of β decreases (the green dotted line changing to a green solid line). So, when the slope is low enough, α will reach α_a first. Finally, in the process of (d) and (e), advancing movement occurs in the PPS first, and due to this displacement, the decrease of β also slows. On the basis of these four processes, we can predict the changes of the contact angles throughout the whole ratchet motion. Through this prediction, we find that the droplet can conduct directional motion. This illustrates that the main cause of droplet movement through the ratchet strategy is the asymmetric change of CAs α and β induced by the asymmetric structure.





Fig. 9 Experiments using the optimized ratchet cycle with different top plate thicknesses. (a) Time sequence illustrating the water droplet transport generated by the relaxing and squeezing cycles of the combined structure. During the squeezing process, the leading contact line advances towards the PPS, and during the relaxing process, the trailing contact line recedes away from the SPS. The profiles of the experiments and simulations are consistent. Two ratchet cycles are required for the droplets to fully enter the PPS. (b) Comparisons of the moving efficiency of different top plate thicknesses based on the simulations and experiments.



4.2.4 Verification by simulations and experiments. Finally, we verified the above analysis *via* experiments and simulations. The result of the inward motion in the first two cycles after bridge formation is shown in Fig. 5. The bridge is squeezed and relaxed from $H_{\max} = 0.5$ mm to $H_{\min} = 0.3$ mm (marked as the reference condition, which is also point D in Fig. 2b).

In the first cycle, three processes were performed, as shown in Fig. 5a. First, the bridge started to move toward the PPS directly, but the trailing edge remained pinned (A and B in Fig. 5a). Second, the bridge was relaxed. At this stage, since the contact lines were pinned by CAH, no obvious movement of the liquid bridge was observed (from B and C in Fig. 5a). Meanwhile, α and β decreased, and according to the period B and C in Fig. 5b, β (about $140^\circ \text{ mm}^{-1}$) had a faster decreasing speed than that of α (about 50° mm^{-1}). Third, when β quickly reached the receding angle α_r , the trailing edge started to recede towards the PPS (C and D in Fig. 5a), while the leading edge was pinned.

In the second cycle, four processes were performed, as shown in Fig. 5c. Compared with the first cycle, we found that a pinned period occurred at the beginning of the squeezing process. At this stage, the contact line remained pinned while α and β increased. Since α and β were within the CAH interval, no inward motion was observed (the leading edge and trailing edge remained stationary in Fig. 5c). The corresponding CA change processes are shown in Fig. 5d, and it can also be found that β decreased (about $250^\circ \text{ mm}^{-1}$) much faster than did α (about 69° mm^{-1}) during the relaxing process, in addition to β having a faster decreasing speed (about $250^\circ \text{ mm}^{-1}$) in the relaxing process compared to the increasing speed (about 95° mm^{-1}) in the squeezing process. All of these findings are consistent with our previous analysis.

The above example validates our theoretical analysis indicating that the main cause of droplet movement through the ratchet strategy is the asymmetric change of CAs α and β during the squeezing and relaxing process, which has never been mentioned in previous studies. In addition to exploring the reasons why this strategy can be implemented, we have also optimized this method to achieve a higher transport efficiency. We found that the critical factors determining the efficiency of the inward motion mainly include two characteristics.

(a) The length of the “pinned period”: The range of $|\Delta H|$, which is used to overcome the contact line pinning at the beginning of relaxing or squeezing, is an important factor affecting the efficiency.

(b) The “change rate” of ΔX versus $|\Delta H|$ ($|dX/dH|$): when the bridge begins to move, the movement efficiency is determined by the change rate of ΔX versus $|\Delta H|$. A larger $|dX/dH|$ will cause a larger distance of horizontal motion with the same change of $|\Delta H|$, which also means a higher efficiency.

To achieve better inward motion performance of the bridge, the effects of various parameters are discussed and optimized in the following subsections.

4.3 Effect of the parameters on ΔX

4.3.1 Effect of the control parameters (H_0 , ΔH) on ΔX . In this subsection, we discuss the method of optimizing the

motion by varying the control parameters according to the corresponding simulation and experimental results.

The effect of H_0 is first addressed. The motion of the bridge under the reference conditions and with three different values of H_0 (varying from 0.4 mm to 0.6 mm) is demonstrated. The results are shown in Fig. 6, where it can be found that varying H_0 has two main effects on the inward movement. A larger H_0 (0.6 mm, 0.5 mm and 0.4 mm, respectively) corresponds to a smaller pinned period (0.02 mm, 0.04 mm and 0.06 mm, respectively) and a slightly larger $|dX/dH|$ (0.50, 0.48 and 0.44, respectively). These observations can be explained by the pressure difference between the PPS and SPS demonstrated in Section 3.1. As shown in Fig. 2b, points C, D, E, and F represent the situation when $H_0 = 0.6$ mm, $H_0 = 0.5$ mm, $H_0 = 0.4$ mm and $\Delta P = 0$. Since $CF > DF > EF$, a stronger tendency (larger pressure) of inward motion will be caused when H_0 is larger, and then a smaller pinned period and a larger value of $|dX/dH|$ will be produced.

The effects of ΔH are also addressed. The motion of the bridge under the reference conditions and with four different values of ΔH (from 0.1 mm to 0.4 mm) is demonstrated. The results are shown in Fig. 6a, where it can be found that a larger ΔH can increase the inward movement, but when $\Delta H > 0.2$ mm, there are some “inefficient” processes. This is mainly caused by two factors. First, during the squeezing process, according to the pressure analysis in Section 3.1, the force pressure on the droplet will gradually change from inward to outward, which will hinder or even stop the droplet's inward movement into the PPS (shown as the “Inefficient squeezing” part in Fig. 7a). Second, during the relaxing process, the droplets slide on the side surface due to excessive lifting of the top plate ($\Delta H > 0.2$ mm, as shown in Fig. 7b). This downward sliding motion prevents the droplet from moving backward in the SPS. This greatly reduces the efficiency of the droplets' entry into the PPS (“Sliding part” in Fig. 7a). Thus, it is crucial to find the appropriate ΔH to achieve efficient droplet movement.

4.3.2 Effect of the thickness of the top plate on ΔX . Because a greater θ_a can promote inward motion (as explained in Section 3.1), we estimate that a thinner top plate (has a similar function of larger θ_a) will produce a better drive performance. We verify this idea through simulations. As shown in Fig. 8, the value of ΔX versus $|\Delta H|$ is plotted for the same situation as used for the reference point but with three different values of H_{UP} . It can be found that varying H_{UP} has two main effects on the inward movement. A smaller H_{UP} (0.2 mm, 0.3 mm and no limit, respectively) corresponds to a smaller pinned period (0.00 mm, 0.02 mm and 0.05 mm, respectively) and a larger $|dX/dH|$ (1.25, 0.75 and 0.31, respectively). Therefore, the results prove our idea that a better performance can be achieved with a thinner top plate during the whole ratchet cycle.

4.4 Optimizing the ratchet cycle by adjusting the parameters

Finally, experiments with optimized parameters were carried out ($V = 1.5 \mu\text{L}$ and $H_{\text{UP}} = 0.6$ mm) to verify our analysis. In these experiments, the top/bottom surfaces were hydrophobic-treated ($\alpha_a \approx 100^\circ$, $\alpha_{\text{CAH}} \approx 20^\circ$), while the side surface was untreated ($\theta_a \approx 75^\circ$, $\theta_{\text{CAH}} \approx 30^\circ$). As shown in Fig. 9a, when we



chose an appropriate H range (0.5–0.9 mm) so that the droplets could move directionally through ratchet-like motion with high efficiency, two ratchet cycles were required for the droplets to fully enter the PPS. The simulations were consistent with the experiments (the profiles of the simulation and experimental results were consistent). To highlight the better performance of the thin top plate, the moving distance (ΔX) of the liquid bridge with a limited (0.6 mm) and a sufficient top plate thickness were compared through simulations and experiments. The results are shown in Fig. 9b, where it can be found that a smaller H_{UP} (0.6 mm and no limit, respectively) corresponds to a smaller pinned period (0.03 mm and 0.06 mm, respectively) and a larger $|dX/dH|$ (0.50 and 0.31, respectively), which is consistent with our analysis above.

5. Conclusions

In summary, experimental and numerical approaches, as well as a theoretical analysis, were employed to study the process of a droplet moving into hydrophobic parallel plates. A ratchet-like strategy was used for the first time to transport the droplets into the hydrophobic parallel plates. In this work, from a static point of view, we analyzed the force applied to the droplet. Afterward, we provided the reason that why this strategy can achieve droplet entry into the PPS from the theoretical point of view, which was verified by experiments and simulations. Then, the functions of the control parameters (H_0 , ΔH) and the thickness of the top plate regarding the efficiency of the movement were researched. Finally, an optimized ratchet cycle was carried out to verify our analysis.

Compared with previous studies,^{25,30,31,37,38} the present strategy provides the following new advances.

(a) A new method of transporting droplets into hydrophobic parallel plates was proposed. Since only mechanical forces are required, this means that no electric fields or other methods that might affect biological or chemical substances are needed, making the method safer for many biochemical applications.

(b) We creatively put forward that the asymmetric change of the CAs induced by the asymmetric structure is the fundamental cause of this kind of motion.

(c) The length of the chord is used for the first time to express the change rate of the contact angle, from which we can easily determine whether the directional motion of the liquid bridge can be achieved by such a ratchet or ratchet-like strategy.

Conflicts of interest

There are no conflicts to declare.

Acknowledgements

Authors acknowledge financial support from National Key R&D Program of China (2018YFB1304905), Natural Science Foundation of the Jiangsu Higher Education Institutions of China (17KJA460008) and Natural Science Foundation of Jiangsu Province of China (BK20171215).

References

- 1 L. Shang, Y. Cheng and Y. Zhao, Emerging Droplet Microfluidics, *Chem. Rev.*, 2017, **117**, 7964–8040.
- 2 C. Liu, J. Sun, J. Li, C. Xiang, L. Che, Z. Wang and X. Zhou, Long-range spontaneous droplet self-propulsion on wettability gradient surfaces, *Sci. Rep.*, 2017, **7**, 7552.
- 3 Y. H. Lai, J. T. Yang and D. B. Shieh, A microchip fabricated with a vapor-diffusion self-assembled-monolayer method to transport droplets across superhydrophobic to hydrophilic surfaces, *Lab Chip*, 2010, **10**, 499–504.
- 4 F. Brochard, Motions of droplets on solid surfaces induced by chemical or thermal gradients, *Br. J. Clin. Psychol.*, 1995, **34**(pt 2), 193–213.
- 5 H. Linke, B. J. Alemán, L. D. Melling, M. J. Taormina, M. J. Francis, C. C. Dow-Hygelund, V. Narayanan, R. P. Taylor and A. Stout, Self-propelled Leidenfrost droplets, *Phys. Rev. Lett.*, 2006, **96**, 154502.
- 6 J. Li, Y. Hou, Y. Liu, C. Hao, M. Li, M. K. Chaudhury, S. Yao and Z. Wang, Directional transport of high-temperature Janus droplets mediated by structural topography, *Nat. Phys.*, 2016, **12**, 606–612.
- 7 J. Wu, R. Ma, Z. Wang and S. Yao, Do droplets always move following the wettability gradient?, *Appl. Phys. Lett.*, 2011, **98**, 159.
- 8 A. H. Ng, B. B. Li, M. D. Chamberlain and A. R. Wheeler, Digital Microfluidic Cell Culture, *Annu. Rev. Biomed. Eng.*, 2015, **17**, 91–112.
- 9 A. H. Ng, M. Lee, K. Choi, A. T. Fischer, J. M. Robinson and A. R. Wheeler, Digital microfluidic platform for the detection of rubella infection and immunity: a proof of concept, *Clin. Chem.*, 2015, **61**, 420–429.
- 10 H.-H. Shen, S.-K. Fan, C.-J. Kim and D.-J. Yao, EWOD microfluidic systems for biomedical applications, *Microfluid. Nanofluid.*, 2014, **16**, 965–987.
- 11 C. Peng, Z. Zhang, C. J. Kim and Y. S. Ju, EWOD (electrowetting on dielectric) digital microfluidics powered by finger actuation, *Lab Chip*, 2014, **14**, 1117–1122.
- 12 T. Banno, R. Kuroha and T. Toyota, pH-Sensitive self-propelled motion of oil droplets in the presence of cationic surfactants containing hydrolyzable ester linkages, *Langmuir*, 2012, **28**, 1190–1195.
- 13 P. Sartori, D. Quagliati, S. Varagnolo, M. Pierno, G. Mistura, F. Magaletti and C. M. Casciola, Drop motion induced by vertical vibrations, *New J. Phys.*, 2015, **17**, 113017.
- 14 S. Mettu and M. K. Chaudhury, Motion of liquid drops on surfaces induced by asymmetric vibration: role of contact angle hysteresis, *Langmuir*, 2011, **27**, 10327–10333.
- 15 K. John and U. Thiele, Self-ratcheting Stokes drops driven by oblique vibrations, *Phys. Rev. Lett.*, 2010, **104**, 107801.
- 16 L. Dong, A. Chaudhury and M. K. Chaudhury, Lateral vibration of a water drop and its motion on a vibrating surface, *Eur. Phys. J. E: Soft Matter Biol. Phys.*, 2006, **21**, 231–242.
- 17 P. Brunet, J. Eggers and R. D. Deegan, Motion of a drop driven by substrate vibrations, *Eur. Phys. J.: Spec. Top.*, 2009, **166**, 11–14.



- 18 P. Brunet, J. Eggers and R. D. Deegan, Vibration-induced climbing of drops, *Phys. Rev. Lett.*, 2007, **99**, 144501.
- 19 S. Sadeghi, H. Ding, G. J. Shah, S. Chen, P. Y. Keng, C. J. Kim and R. M. van Dam, On chip droplet characterization: a practical, high-sensitivity measurement of droplet impedance in digital microfluidics, *Anal. Chem.*, 2012, **84**, 1915–1923.
- 20 B. Hadwen, G. R. Broder, D. Morganti, A. Jacobs, C. Brown, J. R. Hector, Y. Kubota and H. Morgan, Programmable large area digital microfluidic array with integrated droplet sensing for bioassays, *Lab Chip*, 2012, **12**, 3305–3313.
- 21 E. Samiei, M. Tabrizian and M. Hoorfar, A review of digital microfluidics as portable platforms for lab-on a-chip applications, *Lab Chip*, 2016, **16**, 2376–2396.
- 22 G. Wang, D. Teng, Y. T. Lai, Y. W. Lu, Y. Ho and C. Y. Lee, Field-programmable lab-on-a-chip based on microelectrode dot array architecture, *IET Nanobiotechnol.*, 2014, **8**, 163–171.
- 23 A. T. Paxson and K. K. Varanasi, Self-similarity of contact line depinning from textured surfaces, *Nat. Commun.*, 2013, **4**, 1492.
- 24 X. Heng and C. Luo, Bioinspired Plate-Based Fog Collectors, *ACS Appl. Mater. Interfaces*, 2014, **6**, 16257–16266.
- 25 J. Berthier, *Microdrops and Digital Microfluidics*, 2008.
- 26 I. Moon and J. Kim, Using EWOD (electrowetting-on-dielectric) actuation in a micro conveyor system, *Sens. Actuators, A*, 2006, **130–131**, 537–544.
- 27 S. Daniel, S. Sircar, J. Gliem and M. K. Chaudhury, Ratcheting motion of liquid drops on gradient surfaces, *Langmuir*, 2004, **20**, 4085–4092.
- 28 M. Prakash, D. Quere and J. W. Bush, Surface tension transport of prey by feeding shorebirds: the capillary ratchet, *Science*, 2008, **320**, 931–934.
- 29 P. Concus and R. Finn, Discontinuous behavior of liquids between parallel and tilted plates, *Phys. Fluids*, 1998, **10**, 39–43.
- 30 M. Ataei, T. Tang and A. Amirfazli, Motion of a liquid bridge between nonparallel surfaces, *J. Colloid Interface Sci.*, 2017, **492**, 218–228.
- 31 Y. Huang, L. Hu, W. Chen, X. Fu, X. Ruan and H. Xie, Directional Transport of a Liquid Drop between Parallel-Nonparallel Combinative Plates, *Langmuir*, 2018, **34**, 4484–4493.
- 32 X. Heng and C. Luo, Liquid drop runs upward between two nonparallel plates, *Langmuir*, 2015, **31**, 2743–2748.
- 33 C. Luo, X. Heng and M. Xiang, Behavior of a liquid drop between two nonparallel plates, *Langmuir*, 2014, **30**, 8373–8380.
- 34 L. Wang, H. Wu and F. Wang, Efficient transport of droplet sandwiched between saw-tooth plates, *J. Colloid Interface Sci.*, 2016, **462**, 280–287.
- 35 S. H. Collicott and M. M. Weislogel, Computing existence and stability of capillary surfaces using surface evolver, *AIAA J.*, 2004, **42**, 289–295.
- 36 M. J. Santos and J. A. White, Theory and Simulation of Angular Hysteresis on Planar Surfaces, *Langmuir*, 2011, **27**, 14868–14875.
- 37 W. Wang and T. B. Jones, Moving droplets between closed and open microfluidic systems, *Lab Chip*, 2015, **15**, 2201–2212.
- 38 M. Ataei, H. Chen and A. Amirfazli, Behavior of a Liquid Bridge between Nonparallel Hydrophobic Surfaces, *Langmuir*, 2017, **33**, 14674–14683.

