

# PCCP

Accepted Manuscript



This is an *Accepted Manuscript*, which has been through the Royal Society of Chemistry peer review process and has been accepted for publication.

*Accepted Manuscripts* are published online shortly after acceptance, before technical editing, formatting and proof reading. Using this free service, authors can make their results available to the community, in citable form, before we publish the edited article. We will replace this *Accepted Manuscript* with the edited and formatted *Advance Article* as soon as it is available.

You can find more information about *Accepted Manuscripts* in the [Information for Authors](#).

Please note that technical editing may introduce minor changes to the text and/or graphics, which may alter content. The journal's standard [Terms & Conditions](#) and the [Ethical guidelines](#) still apply. In no event shall the Royal Society of Chemistry be held responsible for any errors or omissions in this *Accepted Manuscript* or any consequences arising from the use of any information it contains.

# Computational screening of structural and compositional factors for electrically conductive coordination polymers

*Davide Tiana,<sup>a</sup> Christopher H. Hendon,<sup>a</sup> Aron Walsh,<sup>a\*</sup> and Thomas P. Vaid<sup>b\*</sup>*

<sup>a</sup> Department of Chemistry, University of Bath, Claverton Down, Bath BA2 7AY, UK.

<sup>b</sup> Department of Chemistry, The University of Alabama, Tuscaloosa, Alabama 35487, USA.

\*To whom correspondence should be addressed: a.walsh@bath.ac.uk, tpvaid@ua.edu

## ABSTRACT

The combination of organic and inorganic chemical building blocks to form metal-organic frameworks (MOFs) offers opportunities for producing functional materials suitable for energy generation, storage and conversion. However, such applications rely on robust electron transport and the design of conductive hybrid materials is still in its infancy. Here we apply density functional theory to assess the important structural and compositional factors for forming conducting MOFs. We focus on 1D metal-organic polymers as a model system and assess the choice of organic, inorganic and linking units. The results demonstrate that electronic communication is sensitive to the energy and symmetry of the frontier orbitals associated with the organic and inorganic building blocks and offers guidance on how to optimise electronic communication in hybrid materials.

## 1. INTRODUCTION

Metal-organic frameworks (MOFs) are crystalline materials that consist of metal atoms or clusters linked by polydentate organic ligands to form extended networks, and they now constitute a very large class of materials, with thousands of reported examples.<sup>1-4</sup> The term MOF is often (but not always) taken to imply that the material is porous,<sup>5</sup> but we will use the term herein to refer to all hybrid organic-inorganic frameworks and coordination polymers, whether porous or not. Most of the research on MOFs has examined applications that require porosity, such as gas storage<sup>6</sup> or sensing,<sup>7</sup> and that may be due, in part, to the fact that the vast majority of MOFs are electrically and magnetically uninteresting (*i.e.*, they are electrical insulators and either diamagnetic or paramagnetic). For example, the prototypical MOF, MOF-5, has a measured<sup>8</sup> and calculated<sup>9</sup> band gap of about 3.5 eV, and some nickel-pyrazolate MOFs have calculated band gaps of 3.3-3.4 eV.<sup>10</sup> An electrically conducting porous MOF would have a greatly expanded range of possible applications, as, for instance, high-capacity electrodes for supercapacitors or batteries, size-selective electrodes for electrocatalysis, or gas sensor materials with an easily transduced signal (electrical resistance). Even non-porous electrically conducting MOFs are of interest, since their physical properties (*e.g.* electronic band gap) are tunable through changes in the structure and composition of the organic bridging ligand, while the physical properties of traditional inorganic semiconductors are not tunable in that way.<sup>11,12</sup> At the same time, MOFs have an extended ordered network of covalent bonds, and a semiconducting MOF is therefore likely to have higher carrier mobility than an organic semiconductor, which relies upon intermolecular electron transfer for charge movement. MOFs are now beginning to be incorporated in electronic devices, but primarily as passive, electrically insulating scaffolds.<sup>13</sup>

While the search for electrically conducting MOFs is an active area of research, only a few scattered examples have been reported. The ligand pyrazine-2,3-dithiolate (pdt) forms square planar coordination complexes with copper and Ni,  $[\text{Cu}(\text{pdt})_2]^-$  and  $[\text{Ni}(\text{pdt})_2]^-$ , which react with CuI to form the framework materials  $\text{Cu}[\text{Cu}(\text{pdt})_2]$  and  $\text{Cu}[\text{Ni}(\text{pdt})_2]$ ,<sup>14,15</sup> respectively, both of which are semiconductors. Ni and pyrimidine-2-thiolate form a two-dimensional network  $[\text{Ni}(\text{C}_4\text{N}_2\text{H}_3\text{S})_2]_n$  that is semiconducting.<sup>16</sup> A somewhat related compound is formed between silver and pyridine-2-thiolate,  $[\text{Ag}(\text{C}_5\text{NH}_4\text{S})]_n$ , which is also semiconducting, but it is possible that the conductivity in that case is due to direct Ag-Ag interactions.<sup>17</sup> The silver salt of the dianion of cyanuric acid,  $[\text{Ag}_2\text{C}_3\text{N}_3\text{O}_3\text{H}]_n$ , adopts a three-dimensional network structure that includes two-dimensional silver sheets with particularly short Ag-Ag contacts.<sup>18</sup>  $[\text{Ag}_2\text{C}_3\text{N}_3\text{O}_3\text{H}]_n$  is semiconducting, and in this case the conductivity cannot be due solely to Ag-Ag interactions, as it is conducting both parallel and perpendicular to the Ag sheets. Ni forms one-dimensional coordination polymers with both 6-mercaptopurine and 6-thioguanine, and both of them are semiconducting.<sup>19</sup> Hybrid networks containing  $\text{Cu}^+$ ,  $\text{Cu}^{2+}$ , or  $\text{Ag}^+$  and 1,4-benzenedithiolate<sup>20</sup> or  $\text{Fe}^{2+}$ ,  $\text{Ni}^{2+}$ , or  $\text{Cu}^{2+}$  and 1,2,4,5-benzenetetrathiolate<sup>21</sup> are semiconducting, but none of those materials are crystalline, and were not structurally characterized. Several networks or polymers containing  $\text{Ni}^{2+}$  and  $\text{C}_2\text{S}_4^{2-}$ ,  $\text{C}_4\text{S}_4^{2-}$ ,  $\text{C}_4\text{S}_6^{2-}$ ,  $\text{C}_4\text{S}_8^{2-}$ ,  $\text{C}_6\text{H}_2\text{S}_4^{2-}$ , or  $\text{C}_6\text{S}_8^{2-}$  are semiconducting, but they are also all amorphous.<sup>22-26</sup> The compound formed between  $\text{Pb}^{2+}$  and benzenehexathiolate,  $[\text{Pb}_3(\text{C}_6\text{S}_6)]_n$ , is crystalline with a three-dimensional network structure and is semiconducting.<sup>27,28</sup> Several conjugated organic systems containing multiple cyano groups (tetracyanoethylene, TCNE; 7,7,8,8-tetracyanoquinodimethane, TCNQ; 1,2,4,5-tetracyanobenzene, TCNB; *N,N'*-dicyanoquinonediimine DCNQI) have been used to form networks with various metal ions, and several of those are electrically conducting.<sup>29-34</sup> Most recently, Yaghi and co-workers have

reported two porous conducting MOFs, one containing copper and hexahydroxytriphenylene<sup>35</sup> and the other iron and 1,2,3-triazole.<sup>36</sup>

Other crystalline, electrically conducting materials containing both organic and inorganic components are known, but do not fulfil all of the criteria for the MOFs we are considering herein. For example, an intriguing set of compounds are known that contain one-dimensional chains or two-dimensional sheets of II-VI semiconductors such as ZnTe or CdSe with diamine ligands such as 1,3-propanediamine (pda) that chelate each metal atom along the one-dimensional inorganic chains in ZnTe(pda), or the diamine ligand bridges between two-dimensional inorganic sheets as in CdSe(pda)<sub>0.5</sub>.<sup>37</sup> In those materials the organic component is electrically insulating and serves mainly a structural role; in a conducting MOF the organic “struts” must have a conjugated  $\pi$ -system that can, in principle, support electronic communication between the inorganic “nodes.” In a recent report tetrathiafulvalene-tetrabenzoate (H<sub>4</sub>TTFTB) was used to synthesize the porous MOF Zn<sub>2</sub>(TTFTB), in which TTF moieties are held in a helical stack with a closest S...S contact of 3.803(2) Å.<sup>38</sup> While Zn<sub>2</sub>(TTFTB) has low bulk powder conductivity, it has a reasonable carrier mobility of 0.2 cm<sup>2</sup>/V·s, almost certainly along the TTF stacks. In Zn<sub>2</sub>(TTFTB) the organic component is conducting and the inorganic (Zn-carboxylate) component is insulating, essentially the inverse of the situation in the CdSe(pda)<sub>0.5</sub>-type materials. We hope to discover organic struts and inorganic nodes that can be combined to form MOFs wherein the carrier mobility is high through the entire inorganic-organic system, so that when the inorganic and organic components do not form individual continuous networks (as they do not in a typical porous MOF such as MOF-5<sup>39</sup>), electrical conductivity is still possible.

While there are a few examples of (usually non-porous) conducting MOFs, as described above, there is not yet a set of general design principles for the creation of conducting MOFs. The goal of this paper is to provide such a set of principles to lend some guidance for future efforts toward the synthesis of conducting MOFs. We have calculated the electronic structure of a range of model compounds, based on a first-principles density functional theory (DFT) approach, to examine how changes in composition (identity of the metal atom, identity of the atom linking the metal to the organic component) and several other factors (size of the organic  $\pi$ -system, oxidation state of the metal and/or organic system, the presence of heteroatoms within the organic system) affect the predicted electronic structure of the material. We have used one-dimensional polymers as a model, since it is challenging to predict the full three-dimensional structure that will be adopted by a given metal and bridging ligand. The reduction to one dimension also greatly simplifies the analysis of the band structure, as only one dimension in reciprocal space is relevant and all inter-chain interactions are excluded. The trends discovered in our study are expected to provide a solid foundation for understanding the behaviour of analogous two- and three-dimensional frameworks.

## 2. COMPUTATIONAL DETAILS

All calculations were performed using the Quantum Espresso package (version 4.3.2)<sup>40</sup> within the Kohn-Sham DFT formalism. The PW91 exchange-correlation functional<sup>41,42</sup> was employed using ultra-soft pseudopotentials for the core electrons.<sup>43</sup> The electronic structure was optimised at a non-collinear level of theory with the inclusion of spin orbit coupling. For the open-shell transition metals, the spin moment was fully optimised in each case without constraint of the total spin. The kinetic energy wave-function cut-off for the plane-wave basis set was fixed at 45

Ry, whereas the charge density cut-off was set to 450 Ry (see the supporting information for details on the the cut-off converge). During the geometry optimization, the  $\mathbf{k}$ -points were generated using a Monkhorst-Pack grid<sup>44</sup> of  $16 \times 2 \times 2$ , with (1 0 0) being the repeat direction of the polymer. The Marzari-Vanderbilt smearing occupation was used with a value of 0.04 degauss.<sup>45</sup> At this level of theory, the structures and chemical bonding are well described; however, for band gaps we will focus only on qualitative trends as quantitative predictions require the application of appropriate excited-state techniques.

The geometry of all the polymers was optimized with the following steps. First, a single molecule was optimized using the universal force field<sup>46</sup> included in the code Avogadro.<sup>47</sup> The 1D polymer was then built by applying periodic boundary conditions to the optimized molecule in an orthorhombic unit cell, with  $\mathbf{a}$  the polymer repeat direction. The cell vector  $\mathbf{a}$  therefore equals the monomer length, while the  $\mathbf{b}$  and  $\mathbf{c}$  vectors were fixed with a length such that there was a minimum distance of 8 Å between neighbouring chains (all cell parameters are reported in the supporting information). The internal atomic positions as well as the length of cell vector  $\mathbf{a}$  were then relaxed until convergence in the forces was achieved to within 0.001 eV per Å.

### 3. RESULTS AND DISCUSSION


#### (a) Prototype Ni polymers

##### (i) A series of aromatic organic cores in the linking ligand

A logical starting point for our study is a series of polymers related to a set of known metal-organic polymers that are in fact one-dimensional and conducting: the polymers containing  $\text{Ni}^{2+}$  and  $\text{C}_2\text{S}_4^{2-}$ ,  $\text{C}_4\text{S}_4^{2-}$ ,  $\text{C}_4\text{S}_6^{2-}$ ,  $\text{C}_4\text{S}_8^{2-}$ ,  $\text{C}_6\text{H}_2\text{S}_4^{2-}$ , or  $\text{C}_6\text{S}_8^{2-}$  mentioned in the Introduction.<sup>22–26</sup> While none of the known  $[\text{Ni}(\text{C}_x\text{S}_y)]_n$  compounds were crystalline, and their structures therefore could not be

determined by X-ray crystallography, they are generally presumed to be one-dimensional polymers formed by alternating  $\text{Ni}^{2+}$  and  $\text{C}_x\text{S}_y^{2-}$ , with pairs of chelating S atoms from the ligands giving square-planar coordination around  $\text{Ni}^{2+}$ . One study utilized EXAFS (extended X-ray absorption fine structure) and LAXS (large-angle X-ray scattering) to confirm the one-dimensional chain structure for  $[\text{Ni}(\text{C}_2\text{S}_4)]_n$ ,  $[\text{Ni}(\text{C}_4\text{S}_4)]_n$ , and  $[\text{Ni}(\text{C}_6\text{S}_8)]_n$ .<sup>23</sup>

The series of aromatic polymers examined have the chemical formula  $\text{Na}_2[\text{Ni}(\text{C}_x\text{H}_y\text{S}_4)]_n$ , where the hydrocarbon core of the ligand is ethylene, benzene, naphthalene, anthracene, tetracene, or pentacene, the first three of which are shown in Figure 1. The  $\text{Na}^+$  ions are present in this series to set a charge of 4- on the  $\text{C}_x\text{H}_y\text{S}_4$  ligands and maintain the aromaticity of their organic cores. The oxidation state of the ligands in this series is different from the known conducting polymers just mentioned; polymers with tetrathiolate ligands with a charge of 2- will be discussed later.




**Figure 1.** Three of the  $\text{Na}_{2n}[\text{Ni}(\text{C}_x\text{H}_y\text{S}_4)]_n$  polymers studied, with the axis system used throughout this paper.  $\text{Na}^+$  counterions are omitted for clarity reason.


We first calculated the molecular orbitals (MOs) of the isolated neutral tetrathiol ligands (ethylenetetrathiol, 1,2,4,5-benzenetetrathiol, etc.) so that we could examine the orbitals on the ligand that will interact with Ni. Images of the highest occupied molecular orbital (HOMO), lowest unoccupied molecular orbital (LUMO), and the MO immediately lower in energy than the HOMO (*i.e.*, HOMO-1) for each molecule are shown in Figure 2, while Figure 3 shows the energies of several MOs for each molecule. For all of the organothiol ligands, the S atoms have



$p_z$  orbitals that are a significant component of the HOMO-1, HOMO, and LUMO, and these S  $p_z$  orbitals will interact with the Ni atoms in the polymers. The relative phase of the two S  $p_z$  orbitals on the same side (right or left) of the ligand will determine which of the Ni  $d$  orbitals are of the proper symmetry for interaction when Ni is coordinated by a square planar arrangement of S atoms in the polymer. When the S  $p_z$  orbitals are of the same phase, then the Ni  $d_{xz}$  orbitals (see Figure 1 for the axis system) will interact. When the S  $p_z$  orbitals are of the opposite phase to each other, then the Ni  $d_{yz}$  orbitals will interact. The Ni  $d_{z^2}$ ,  $d_{xy}$ , and  $d_{x^2-y^2}$  orbitals are expected to have no net interaction with the S  $p_z$  orbitals in either case.



**Figure 2.** Molecular orbitals of ethylenetetrahiol, 1,2,4,5-benzenetetrahiol, 2,3,6,7-naphthalenetetrahiol, etc., with the number of rings ( $r$ ) indicated above each set of orbitals. Atoms colour: C = brown, S = yellow, H = beige.



**Figure 3.** Molecular orbital energies for the tetrathiol ligands of Figure 2. The black lines denote HOMOs and LUMOs. The vacuum level is set to 0 eV.

Many of the tetrathiol ligand MOs are observed, almost unaltered, in the electron density distributions of the  $\text{Na}_{2n}[\text{Ni}(\text{C}_x\text{H}_y\text{S}_4)]_n$  bands, as shown in Figure 4 (all the electron distributions in Figure 4 are at the  $\Gamma$  point in reciprocal space). A summary of the band gaps and highest occupied crystal orbital (HOCO) and lowest-unoccupied crystal orbital (LUCO) band dispersions are given in Table 1. For the ethylene core ( $r = 0$ , for zero fused rings), the  $S p_z$  orbitals of the ligand interact with the Ni  $d_{xz}$  atomic orbital to form the extended HOCO of the polymer. The polymer LUCO is a ligand-field state that comprises mainly the Ni  $d_{xy}$  atomic orbital. The LUCO band dispersion is due to interactions of the directed S atomic orbitals across the ethylenetetrathiolate bridge. The HOCO-1 is formed by a non-bonding Ni  $d_{z^2}$  orbital.


For the benzene core ( $r = 1$ ), the HOMO of the ligand again interacts with the Ni  $d_{xz}$  to form the extended HOCO of the polymer, but due to the orbital symmetry the valence band maximum (antibonding interaction) is at the  $\Gamma$  point. The HOMO-1 of the ligand combines with the Ni  $d_{yz}$

to form the extended HOCO-1 of the polymer. The polymer LUCO is a ligand-field state that comprises mainly the Ni  $d_{xy}$  atomic orbital; this leads to a flat LUCO band, with a calculated dispersion of only 0.07 eV. The LUCO+1 band is simply the ligand LUMO.

For  $r = 2$  (the naphthalene core), the tetrathiol LUMO and a small component of the Ni  $d_{xz}$  combine to form the LUCO+1. The polymer LUCO is a ligand-field state that comprises mainly the Ni  $d_{xy}$  atomic orbital; this leads to a very flat LUCO band, with a calculated dispersion of only 0.04 eV. Again, the HOCO and HOCO-1 states are formed of combination of the Ni  $d_{xy}$  and  $d_{yz}$  orbitals, respectively. For  $r = 2a$  (the naphthalene core with Ss attached to different carbon atoms, so that the naphthalene core is rotated by  $90^\circ$ ), the polymer HOCO-1 is simply the ligand HOMO, while the polymer HOCO is formed from the combination of the ligand HOMO-1 with the Ni  $d_{xz}$ . The LUCO is the Ni  $d_{xy}$  atomic orbital, while the LUCO+1 is the combination of the ligand LUMO and the Ni  $d_{yz}$ .

For  $r = 3$  (the anthracene core) the polymer HOCO is formed from the combination of the ligand HOMO with the Ni  $d_{xz}$ . The LUCO is the Ni  $d_{xy}$  ligand-field state, while the LUCO+1 is the ligand LUMO. For  $r = 4$  (the tetracene core) the polymer HOCO-1 is the ligand HOMO. The polymer HOCO is the combination of the Ni  $d_{xz}$  and the ligand HOMO-2 (not shown in Figure 2). The LUCO is the combination of the ligand LUMO and a small contribution from the Ni  $d_{xz}$ , while the LUCO+1 is the Ni  $d_{xy}$  ligand-field state. For  $r = 4a$  (the pyrene core) the polymer HOCO is the combination of the ligand HOMO and Ni  $d_{xz}$ , while the LUCO is the Ni  $d_{xy}$  ligand-field state and the LUCO+1 is the ligand LUMO. For  $r = 5$  (the pentacene core) the polymer HOCO is the combination of the ligand HOMO and Ni  $d_{yz}$ . The LUCO is the ligand LUMO, while the LUCO+1 is the Ni  $d_{xy}$  ligand-field state.

In the series  $r = 1 - 5$  there is an important change that occurs between  $r = 3$  and  $r = 4$ . For  $r = 1, 2,$  and  $3$  the LUCO is comprised of the antibonding combination of Ni  $d_{xy}$  orbital and four in-plane S  $p$ -orbitals directed toward Ni, which form a flat, localized band. The LUCO+1 consists of the ligand LUMO state of Figure 2. As the number of fused rings increases, the energy of the ligand LUMO decreases, such that for  $r = 4$  and  $5$  it is the polymer LUCO. Such a transition could result in an abrupt change from band to hopping conductivity.




**Figure 4.** Electron distribution (at the  $\Gamma$  point) of the HOCO-1, HOCO, LUCO, and LUCO+1, and band structures of the  $\text{Na}_2[\text{Ni}(\text{C}_x\text{S}_y)]_n$  polymers. The top of the valence band is set to 0, the band energies are in eV, and the Na contribution to the band structures are drawn as dotted lines. Atoms colour: Ni = bright green, C = brown, S = yellow, H = beige, Na = dark grey.

**Table 1** Summary of calculated properties of the  $\text{Na}_{2n}[\text{Ni}(\text{C}_x\text{S}_y)]_n$  compounds. D and I refer to direct and indirect band gaps, respectively.

| Organic Component    | $r$ | $E_g$ (eV) | HOCO dispersion | LUCO dispersion | $E_g$ Classification |
|----------------------|-----|------------|-----------------|-----------------|----------------------|
| Ethylene             | 0   | 1.45       | 0.78            | 0.72            | D                    |
| Benzene              | 1   | 1.01       | 0.55            | 0.07            | I                    |
| Naphthalene          | 2   | 1.10       | 0.39            | 0.04            | D                    |
| Anthracene           | 3   | 1.20       | 0.29            | 0.02            | I                    |
| Tetracene            | 4   | 1.02       | 0.22            | 0.22            | D                    |
| Pentacene            | 5   | 0.46       | 0.15            | 0.30            | D                    |
| Naphthalene, side-on | 2a  | 1.19       | 0.43            | 0.22            | I                    |
| Pyrene               | 4a  | 1.15       | 0.09            | 0.13            | D                    |

(ii) *Effects of changing the linking chalcogen*

In inorganic semiconductors the identity of the anion has a significant effect on the electronic properties. For a given metal, the band gap generally (though not always) decreases along the chalcogenide series: oxide to sulfide to selenide to telluride. In order to examine the effects of the element that forms the bond to the metal in the one-dimensional models, we have performed calculations on the set of compounds  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{O}_4)]_n$ ,  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{S}_4)]_n$ , and  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{Se}_4)]_n$ , where  $\text{C}_{22}\text{H}_{10}$  is the pentacene core (see Figure 1 for the polymer structure). The band gaps and HOCO and LUCO dispersions are given in Table 2, and the bands and electron density distributions for the HOCO and LUCO are shown in Figure 5. For  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{S}_4)]_n$  the results were discussed earlier: the Ni  $d_{yz}$  and pentacenetetrathiolate HOMO form the polymer HOCO, while the pentacenetetrathiolate LUMO forms the polymer LUCO. The Se version,  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{Se}_4)]_n$ , is very similar, with an almost identical band gap and slightly reduced HOCO and LUCO dispersions.



**Figure 5.** Electron distribution (at the  $\Gamma$  point) of the HOCO, LUCO and band structures for oxygen, S and Se bridging substituents, respectively. The band energies are given in eV. Atoms colour: Ni = bright green, C = brown, S = yellow, H = beige, O = red, Se = pea green, Na = dark grey.


**Table 2.** Electronic properties of  $r = 1$  and 5 polymers with oxygen, S and Se bridging substituents. D and I refer to direct and indirect bands gaps, respectively.

| Linker | Organic Ligand | $E_g$ (eV) | HOCO dispersion | LUCO dispersion | $E_g$ Classification |
|--------|----------------|------------|-----------------|-----------------|----------------------|
| O      | Benzene        | 0.72       | 0.76            | 0.05            | D                    |
| S      | Benzene        | 1.01       | 0.55            | 0.07            | I                    |
| Se     | Benzene        | 1.01       | 0.41            | 0.02            | I                    |
| O      | Pentacene      | 0.90       | 0.16            | 0.00            | D                    |
| S      | Pentacene      | 0.74       | 0.15            | 0.20            | D                    |
| Se     | Pentacene      | 0.74       | 0.14            | 0.16            | D                    |

When oxygen is the connecting element, in  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{O}_4)]_n$ , the identity of the polymer LUCO is different from that in the S and Se versions. As can be seen in Figure 5, the  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{O}_4)]_n$  LUCO is a local Ni  $d_{xy}$  ligand field state. This localized state gives essentially no band dispersion. The same ligand field state is visible in the band diagrams of  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{S}_4)]_n$  and  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{Se}_4)]_n$  in Figure 5, where it is the flat LUCO+1 band. The

greater electronegativity of oxygen places this band at lower energy in  $\text{Na}_{2n}[\text{Ni}(\text{C}_{22}\text{H}_{10}\text{O}_4)]_n$ , where it becomes the LUCO.

In the set of compounds in which benzene is the organic core, the polymer HOCO results from interaction of the Ni  $d_{xz}$  and the ligand HOMO in all cases (O, S, and Se). The HOCO dispersions (see



**Figure 6.** Benzene-1,2,4,5-tetrathiolate in the 2- (quinoid) oxidation state.

Table 2) are significantly larger than for the pentacene-based polymer, and largest with oxygen as the linking atom. The LUCO is the Ni  $d_{xy}$  ligand field state for all linking elements, and all of the LUCO bands therefore have low dispersion.

The implication of these results in the synthesis of conducting MOFs depends partly upon the identity of the organic core of the ligand. For all linking atoms and both organic cores, the HOCO had some dispersion, which implies that with appropriate oxidative doping all would be reasonable  $p$ -type conductors. With a small conjugated organic system (represented by benzene here), the LUCO is always a ligand field state, so it is unlikely that good  $n$ -type conductivity can be achieved. With a larger conjugated organic system (represented by pentacene here), with S or Se as the linking atom a LUCO with band dispersion results. With appropriate reductive doping an  $n$ -type conductor could be obtained. In fact, for the pentacene core and S or Se linking atoms, the band gap is less than 1 eV and hence intrinsic conductivity is possible.

### *(iii) Effects of oxidizing the ligands to the quinoid state*

As noted above, all of the Ni-arenetetrachalogenide polymers had HOCO bands with moderate dispersion, so in all cases oxidative doping should yield  $p$ -type conductors with good hole mobility. Oxidizing the polymers by two electrons per repeat unit would yield systems in which the organic linker has an oxidation state of 2-, as represented by the resonance structures in




Figure 6. In the known conducting Ni-tetrathiolate polymers cited above, the oxidation state of the ligands is, in fact (at least nominally), 2-. We performed calculations on the  $[\text{Ni}(\text{C}_x\text{H}_y\text{S}_4)]_n$  series of polymers where the hydrocarbon core ranged from benzene ( $r = 1$ ) to pentacene ( $r = 5$ ). The structures are identical to those in Figure 1, except that there are no  $\text{Na}^+$  counterions present, so that there is no net charge on the Ni-tetrathiolate polymer. To a first approximation, one would expect the LUCO of the oxidized system to resemble the HOCO of the original system, while the oxidized HOCO will resemble the HOCO-1 of the original system. In all cases, we found a very close resemblance in the expected electron density distributions, as shown for  $r = 1$  in Figure 7.

A structural distortion might naively be expected in the oxidized polymers to facilitate localization of the ligand  $\pi$ -bonds in one; such bond-length alternation does occur in undoped polyacetylene.<sup>48</sup> However, in all of the optimized  $[\text{Ni}(\text{C}_x\text{H}_y\text{S}_4)]_n$  structures (from  $r = 1$  to 5) no bond-length alternation occurred; even when an initial distortion was artificially imposed, the system returned to a symmetric structure upon optimization at this level of theory. A quasi-metallic state was found. However, to check if this solution was due to the use of a semi-local exchange-correlation functional, the electronic structure of  $\text{Na}_2[\text{Ni}(\text{C}_6\text{H}_2\text{S}_4)]_n$  and  $[\text{Ni}(\text{C}_6\text{H}_2\text{S}_4)]_n$  were also calculated using the inclusion of 25% non-local exact exchange. Indeed, the metallic behaviour is lost, and a small band gap of 0.43 eV is opened for the quinoid state. However, the orbital contributions to the HOCO and LUCO remain unchanged, and no bond alternation is observed.

Interestingly for this oxidised state, significant band dispersion is observed: both the Ni  $d_{yz}$  and the  $d_{xz}$  orbitals (the metal components of the HOCO and LUCO, respectively) have the appropriate symmetry to overlap with the organic ligand. This results in a dispersion of 0.29 eV


(valence band) and 0.87 eV (conduction band). We can therefore conclude that quinoid systems are likely to have a small band gaps, high carrier mobility, and therefore high conductivity.



**Figure 7.** Electron distribution (at the  $\Gamma$  point) of the HOCO, LUCO for  $\text{Na}_{2n}[\text{Ni}(\text{C}_6\text{H}_2\text{S}_4)]_n$  (left) and  $[\text{Ni}(\text{C}_6\text{H}_2\text{S}_4)]_n$  (right). Note that the HOCO of the aromatic state becomes the LUCO of the oxidized quinoid state. Atoms colour: Ni = bright green, C = brown, S = yellow, H = beige, O = red, Se = pea green, Na = dark grey.

(iv) *Octahedral coordination of Ni by addition of two  $\text{NH}_3$  ligands*

To account for alternative chemical environments, we have also considered octahedral coordination for the metal, which is obtained through the addition of two *trans*- $\text{NH}_3$  ligands to the metal. The compound analysed is thus  $\text{Na}_{2n}[\text{M}(\text{NH}_3)(\text{C}_6\text{H}_2\text{S}_4)]_n$ . Modifying the crystal field acting on the Ni from square planar to octahedral alters the valence orbital configuration. The addition of two axial ligands to the metal de-stabilises the  $d_{z^2}$  orbital, which becomes the HOCO (Figure 8). This reconfiguration impacts the electronic properties: the  $d_{z^2}$  orbital does not have the required symmetry to efficiently overlap with the S  $\pi$  orbitals, reducing the dispersion in the valence band from 0.5 to 0.1 eV. On the other hand, the Ni  $d_{xy}$  orbital is not greatly affected by the addition of axial ligands. Thus the nature of the conduction band does not change moving from a square planar field to an octahedral one, remaining anti-bonding in nature.




**Figure 8.** Electron distribution (at the  $\Gamma$  point) of the HOCO, LUCO for the Ni  $r = 1$  polymer as a function of metal coordination environment. Note that while the LUCO remains unchanged, the additional of axial ligands changes the HOCO from Ni  $d_{xy}$  to  $d_{z^2}$ . Where the metal  $d_{z^2}$  orbital is present, a side-on view is used for clarity. Atoms colour: Ni = bright green, C = brown, S = yellow, H = beige, O = red, Se = pea green, Na = dark grey, N = black spot.

(v) *Other metals*

The effect of changing the metal has been analysed along the first row of the transition metal series. The compounds analysed had the composition  $\text{Na}_{2n}[\text{M}(\text{NH}_3)(\text{C}_6\text{H}_2\text{S}_4)]_n$ , where M is the transition metal. It should be noted that in order to have a systematic analysis, all the metals were analysed with a formal oxidation state of 2+, although some of them do not frequently occur in that oxidation state in nature. However, this survey allows us to assess the electronic behaviour with respect to  $d$  orbital occupation. The most direct change from Sc to Zn is that the  $d$  orbitals become filled (Figure 9); for the divalent metals it is a transition from an electronic configuration of  $d^1$  to  $d^{10}$ . The change in electron count results in a change in the symmetry of the frontier orbitals of the metals, and consequently, the dispersion of the polymer bands. For example, the LUCO of Cr has the same composition as the HOCO of Mn and Fe, with a Cr conduction band dispersion of 0.20 eV comparable with 0.23 eV and 0.24 eV for the valence band of Mn and Fe, respectively. Generally, distinct behaviour is observed for different metal orbitals:  $d_{yz}$  or  $d_{xz}$  (metal-equatorial ligand bond interactions),  $d_{x^2-y^2}$  (metal-metal interactions), whereas flat bands

are observed for the  $d_{z^2}$  (metal-axial ligand bonding interactions) and the  $d_{xy}$  (metal-ligand anti-bonding interaction). Arriving to the Zn HOCO, all of the  $d$  orbitals are filled; thus, electron addition involves the organic ligand orbitals, which become the new LUMO states.



**Figure 9.** Electron distribution (at the  $\Gamma$  point) of the HOCO, LUCO as a function of the  $3d$  metal, in octahedral coordination. The results for Sc, Ti, and V are included for completeness, but the oxidation states do not frequently occur in nature. Where the metal  $d_{z^2}$  orbitals are present, a side-on view is used for clarity. Atoms colour: Ni = bright green, C = brown, S = yellow, H = beige, O = red, Se = pea green, Na = dark grey, N = black spot.

### (b) Other Archetype Systems

The model polymers discussed above allowed a systematic investigation of specific chemical changes on the electronic structure. However, there are several reported organic-inorganic systems that are either semiconducting or were investigated for their possible electrical conductivity, but differ significantly from the structural motif explored above. Some of these were mentioned in the Introduction. The structural motifs can be projected onto one-dimensional polymers that are representative of the three-dimensional hybrid frameworks. This model

approach allows for a direct comparison with the Ni polymers analysed in the previous section. The structures of the prototype systems are shown in Figure 10 and a summary of their properties is given in Table 3.

Several organocyanide-metal networks exhibit electrical conductivity.<sup>29–34</sup> Two model polymers were examined:  $[\text{CuCl}_2(\text{TCNE})]_n$  (**I** in Figure 10) and  $[\text{Cu}(\text{DCNQI})]_n$  (**II** in Figure 10) (TCNE = tetracyanoethylene; DCNQI = *N,N'*-dicyanoquinonediimine). The latter is a metallic conductor at room temperature.<sup>30</sup> When analysing **I**, we found a band gap of 0.67 eV, with the HOCO and the LUCO giving no significant dispersion. Indeed the HOCO is the Cu-Cl bond, while the LUCO consists of the ligand LUMO. We found polymer **II** to be semimetallic with a large dispersion, 0.35 eV, at the Fermi level. This dispersion is due to the overlap of the Cu  $d_{xz}$  orbital with the N  $p_z$  of the cyano group, which further conjugates with the aromatic ring, resulting in an infinite delocalisation along the chain. Thus we can see that the one-dimensional polymers capture the essential features of the band structure.

Another interesting class of hybrid material known to be semiconducting can be found combining heterocyclic thiolates with Cu, Ni, or Ag.<sup>14–17</sup> A representative polymer consisting of  $\text{Ni}^{2+}$  and pyrimidine-4,6-dithiolate (compound **III**) was constructed and its band structure examined. The coordination sphere of  $\text{Ni}^{2+}$  is distorted square planar, with the structure shown in Figure 10. Both the valence and conduction bands have dispersions of 0.18 and 0.27 eV, respectively. The origin of that band dispersion is the Ni  $d_{xz}$  orbital overlap with S  $p_z$ , forming the HOCO, whereas the LUCO is formed by the mixture of the Ni  $d_{x^2-y^2}$  and the N  $p_z$  orbital of the pyrimidine. Furthermore, the calculated band gap is small, 0.45 eV. These numbers corroborate the electrical conductivity reported for several compounds of this type.

The coordination polymer of 2-phenylimidazole and silver (compound **IV**) has been analysed as an analogue of imidazolate frameworks.<sup>49</sup> With a calculated band gap of 3.21 eV and negligible band dispersion, this class of system does not seem to be interesting from a band conduction perspective.

The recent report of a conducting MOF constructed from Fe<sup>2+</sup> and 1,2,3-triazole led us to examine the one-dimensional polymer [Fe(C<sub>2</sub>H<sub>2</sub>N<sub>3</sub>)<sub>2</sub>]<sub>n</sub> (**V**).<sup>36</sup> The moderate band gap (0.78 eV) and band dispersion is consistent with electrical conductivity. The band dispersion arises from metal-metal interactions (Fe...Fe distance 3.7 Å), which are possibly semiconducting, although they were not found to be electrically conductive

An intriguing system that was investigated for its possible conductivity is the cubic network of Cr(1,4-diisocyanobenzene)<sub>3</sub> reported by Yaghi and Choi in a patent.<sup>50</sup> The polymer [Cr(CO)<sub>4</sub>(1,4-diisocyanobenzene)]<sub>n</sub> (**VI**) was examined as a model of that network. Although it has significant band dispersion, its calculated band gap of 1.87 eV is quite large.


Two one-dimensional polymers of tetrathioterephthalate have been reported, [M(S<sub>2</sub>CC<sub>6</sub>H<sub>4</sub>CS<sub>2</sub>)(DMF)<sub>2</sub>]<sub>n</sub> (M = Zn, Mn).<sup>51</sup> While the Mn compound has a visible absorption onset at 925 nm, corresponding to 1.34 eV, no electrical conductivity was reported. We have calculated the electronic structure of both compounds (**VII**; M = Zn, Mn); both have negligible bands dispersion. In the case of Mn, the HOCO and LUCO are the *d*<sub>z<sup>2</sup></sub> and the *d*<sub>x<sup>2</sup>-y<sup>2</sup></sub>, respectively. Such symmetry does not facilitate overlap with the frontier orbitals of the organic ligand. Regarding Zn, as seen in the previous section, the *d* shell is complete and does contribute to the frontier orbitals.

Finally, there is a class of compounds comprising clusters of transition metals (Fe, Co, Zn and Cd) linked into three-dimensional networks by bridging thiolates that have been reported as

semiconducting materials.<sup>52-54</sup> Polymer **VIII**,  $[\text{Zn}(\text{SPh})_2]_n$ , was studied as a model system, and it is the only analysed case where a Zn compound showed significant band dispersion. However, the role of Zn is indirect: the band dispersion arises from S contacts through the metal centre (S...S distance = 3.4 Å). While the role of Zn appears to be structural in this case, it could be partially substituted (*e.g.* by Cu or Al) to enhance the semiconducting behaviour. In a recent example, some of the  $\text{Zn}^{2+}$  sites of MOF-5 were substituted by other transition metal ions, leading to electroactivity.<sup>55</sup>

**Table 3.** Electronic properties of prototype polymers examined. D and I refer to direct and indirect bands gaps, respectively. The corresponding structures are given in Figure 10.

| Compound | Metal | Organic Ligand | $E_g$ (eV) | HOCO dispersion | LUCO dispersion | $E_g$ Classification |
|----------|-------|----------------|------------|-----------------|-----------------|----------------------|
| I        | Cu    | TCNE           | 0.67       | 0.00            | 0.01            | D                    |
| II       | Cu    | DCNQI          | 0.02       | 0.35            | 0.01            | D                    |
| III      | Ni    | Pyrimidine     | 0.45       | 0.18            | 0.27            | D                    |
| IV       | Ag    | Imidazole      | 3.21       | 0.06            | 0.06            | D                    |
| V        | Fe    | Triazole       | 0.78       | 0.07            | 0.11            | D                    |
| VI       | Cr    | Cyanide        | 1.87       | 0.31            | 0.67            | D                    |
| VII      | Mn    | TTPT           | 0.02       | 0.02            | 0.02            | D                    |
| VII      | Zn    | TTPT           | 1.34       | 0.00            | 0.04            | D                    |
| VIII     | Zn    | Thiolate       | 1.43       | 0.29            | 0.26            | D                    |



**Figure 10.** Structures of the archetypal organic-inorganic polymers examined.

#### 4. CONCLUSIONS

From the series of Ni-based polymers studied here a number of conclusions can be drawn:

(1) Excluding the tetracene and pentacene, the LUCOs of the polymer are localized ligand-field states. It is therefore likely that to obtain MOFs with good intrinsic or n-type conductivity, linkers with large conjugated  $\pi$ -systems (and therefore small HOMO-LUMO gaps) will be necessary. This does not rule out the possibility of creating good p-type conductors with the smaller linkers, but doping or other methods will be necessary to create significant carrier concentrations.

(2) Considering oxygen as the standard linking atom (in carboxylates), less electronegative species and “softer” linking atoms such as S or Se (rather than oxygen) generally decrease the band gap and increase the band dispersions of the polymers (and therefore analogous MOFs).



However, the change from S to Se is quite small, and considering the greater synthetic difficulties involved with the use of Se, S may be preferred over Se.

(3) When the organic tetrathiolate linker is oxidized to the 2- oxidation state (quinoid), a polymer with a small band gap and larger band dispersions results. For the simple Ni-benzenetetrathiolate polymer  $[\text{Ni}(\text{C}_6\text{H}_2\text{S}_4)]_n$  the calculated band gap was only 0.43 eV. However, the chemical stability of these oxidised polymers may be an issue.

(4) Changing the coordination sphere of Ni from square planar to octahedral by the addition of two  $\text{NH}_3$  ligands destabilizes the Ni  $d_{z^2}$  orbital, such that it becomes the (localized) HOCO of the polymer. In more general terms, we cannot always predict when a localized ligand-field state will be the HOCO or LUCO of the polymer (or MOF), but a linking ligand with a small HOMO-LUMO gap will more often lead to a material in which both the metal orbitals and those of the  $\pi$ -system of the linker contribute to both the HOCO and LUCO, leading to good band dispersion.

Beyond the Ni polymers, substitution with cations across the transition metal series show a systematic behaviour depending on the  $d$  orbital occupation. The composition of the HOCO and LUCO depend on the symmetry of the occupied and empty  $d$  orbitals, which vary in their hybridisation with the organic ligands. Investigation of a number of other systems that have either been reported to be conducting or proposed as possible conducting materials demonstrate mixed results: the band structures for the 1D analogues are consistent with band conductivity for some, while for others higher order connectivity and topology must be origin of the observed conductivity.

## Acknowledgements

D.T. and C.H.H. are funded under ERC Starting Grant 277757, while A.W. is supported a Royal Society University Research Fellowship and EPSRC Grant EP/K016288/1. The work benefited from the University of Bath's High Performance Computing Facility, and access to the HECToR supercomputer through membership of the UK HPC Materials Chemistry Consortium, which is funded by EPSRC (Grant no. EP/F067496).

## References

- (1) Yaghi, O. M.; O'Keeffe, M.; Ockwig, N. W.; Chae, H. K.; Eddaoudi, M.; Kim, J. *Nature* **2003**, *423*, 705–714.
- (2) O'Keeffe, M.; Peskov, M. A.; Ramsden, S. J.; Yaghi, O. M. *Acc. Chem. Res.* **2008**, *41*, 1782–1789.
- (3) Natarajan, S.; Mahata, P. *Chem. Soc. Rev.* **2009**, *38*, 2304–2318.
- (4) Farha, O. K.; Hupp, J. T. *Acc. Chem. Res.* **2010**, *43*, 1166–1175.
- (5) Batten, S. R.; Champness, N. R.; Chen, X.-M.; Garcia-Martinez, J.; Kitagawa, S.; Öhrström, L.; O'Keeffe, M.; Suh, M. P.; Reedijk, J. *CrystEngComm* **2012**, *14*, 3001.
- (6) Wong-Foy, A. G.; Matzger, A. J.; Yaghi, O. M. *J. Am. Chem. Soc.* **2006**, *128*, 3494–3495.
- (7) Kreno, L. E.; Hupp, J. T.; Van Duyne, R. P. *Anal. Chem.* **2010**, *82*, 8042–8046.
- (8) Alvaro, M.; Carbonell, E.; Ferrer, B.; Llabrés i Xamena, F. X.; Garcia, H. *Chem. Eur. J.* **2007**, *13*, 5106–5112.
- (9) Yang, L.-M.; Vajeeston, P.; Ravindran, P.; Fjellvag, H.; Tilset, M. *Inorg. Chem.* **2010**, *49*, 10283–10290.
- (10) Albanese, E.; Civalleri, B.; Ferrabone, M.; Bonino, F.; Galli, S.; Maspero, A.; Pettinari, C. *J. Mater. Chem.* **2012**, *22*, 22592–22602.
- (11) Hendon, C. H.; Tiana, D.; Walsh, A. *Phys. Chem. Chem. Phys.* **2012**, *14*, 13120–13132.
- (12) Hendon, C. H.; Tiana, D.; Fontecave, M.; Sanchez, C.; D'arras, L.; Sassoie, C.; Rozes, L.; Mellot-Draznieks, C.; Walsh, A. *J. Am. Chem. Soc.* **2013**, *135*, 10942–10945.
- (13) Allendorf, M. D.; Schwartzberg, A.; Stavila, V.; Talin, A. A. *Chem. Eur. J.* **2011**, *17*, 11372–11388.
- (14) Takaishi, S.; Hosoda, M.; Kajiwara, T.; Miyasaka, H.; Yamashita, M.; Nakanishi, Y.; Kitagawa, Y.; Yamaguchi, K.; Kobayashi, A.; Kitagawa, H. *Inorg. Chem.* **2009**, *48*, 9048–9050.
- (15) Kobayashi, Y.; Jacobs, B.; Allendorf, M. D.; Long, J. R. *Chem. Mater.* **2010**, *22*, 4120–4122.
- (16) Zhao, Y.; Hong, M.; Liang, Y.; Cao, R.; Weng, J.; Lu, S.; Li, W. *Chem. Commun.* **2001**, 1020–1021.
- (17) Su, W.; Hong, M.; Weng, J.; Cao, R.; Lu, S. *Angew. Chem. Int. Ed.* **2000**, *39*, 2911–2914.

- (18) Rao, C. N. R.; Ranganathan, A.; Pedireddi, V. R.; Raju, A. R. *Chem. Commun.* **2000**, 39–40.
- (19) Amo-Ochoa, P.; Castillo, O.; Alexandre, S. S.; Welte, L.; de Pablo, P. J.; Rodriguez-Tapiador, I.; Gomez-Herrero, J.; Zamora, F. *Inorg. Chem.* **2009**, *48*, 7931–7936.
- (20) Schrauzer, G. N.; Prakash, H. *Inorg. Chem.* **1975**, *14*, 1200–1204.
- (21) Dirk, C. W.; Bousseau, M.; Barrett, P. H.; Moraes, F.; Wudl, F.; Heeger, A. J. *Macromolecules* **1986**, *19*, 266–269.
- (22) Rivera, N. M.; Engler, E. M.; Schumaker, R. R. *J. Chem. Soc., Chem. Commun.* **1979**, 184.
- (23) Vogt, T.; Faulmann, C.; Soules, R.; Lecante, P.; Mosset, A.; Castan, P.; Cassoux, P.; Galy, J. *J. Am. Chem. Soc.* **1988**, *110*, 1833–1840.
- (24) Faulmann, C.; Cassoux, P.; Vicente, R.; Ribas, J.; Jolly, C. A.; Reynolds, J. R. *Synth. Met.* **1989**, *29*, E557–E562.
- (25) Dahm, S.; Strunz, W.; Keller, H. J.; Schweitzer, D. *Synth. Met.* **1993**, *55*, 884–889.
- (26) Szczepura, L. F.; Galloway, C. P.; Zheng, Y.; Han, P.; Rheingold, A. L.; Wilson, S. R.; Rauchfuss, T. B. *Angew. Chem. Int. Ed.* **1995**, *34*, 1890–1892.
- (27) Turner, D. L.; Vaid, T. P.; Stephens, P. W.; Stone, K. H.; DiPasquale, A. G.; Rheingold, A. L. *J. Am. Chem. Soc.* **2008**, *130*, 14–15.
- (28) Hendon, C. H.; Tiana, D.; Vaid, T. P.; Walsh, A. *J. Mater. Chem. C* **2013**, *1*, 95.
- (29) Kaim, W.; Moscherosch, M. *Coord. Chem. Rev.* **1994**, *129*, 157–193.
- (30) Sinzger, K.; Huenig, S.; Jopp, M.; Bauer, D.; Bietsch, W.; von Schuetz, J. U.; Wolf, H. C.; Kremer, R. K.; Metzenthin, T. *J. Am. Chem. Soc.* **1993**, *115*, 7696–7705.
- (31) Heintz, R. A.; Zhao, H.; Ouyang, X.; Grandinetti, G.; Cowen, J.; Dunbar, K. R. *Inorg. Chem.* **1998**, *38*, 144–156.
- (32) Aumüller, A.; Erk, P.; Klebe, G.; Hünig, S.; von Schütz, J. U.; Werner, H.-P. *Angew. Chem. Int. Ed.* **1986**, *25*, 740–741.
- (33) Avendano, C.; Zhang, Z.; Ota, A.; Zhao, H.; Dunbar, K. R. *Angew. Chem. Int. Ed.* **2011**, *50*, 6543–6547.
- (34) Munakata, M.; Ning, G. L.; Kuroda-Sowa, T.; Maekawa, M.; Suenaga, Y.; Horino, T. *Inorg. Chem.* **1998**, *37*, 5651–5656.
- (35) Hmadeh, M.; Lu, Z.; Liu, Z.; Gándara, F.; Furukawa, H.; Wan, S.; Augustyn, V.; Chang, R.; Liao, L.; Zhou, F.; Perre, E.; Ozolins, V.; Suenaga, K.; Duan, X.; Dunn, B.; Yamamoto, Y.; Terasaki, O.; Yaghi, O. M. *Chem. Mater.* **2012**, *24*, 3511–3513.
- (36) Gándara, F.; Uribe-Romo, F. J.; Britt, D. K.; Furukawa, H.; Lei, L.; Cheng, R.; Duan, X.; O’Keeffe, M.; Yaghi, O. M. *Chem. Eur. J.* **2012**, *18*, 10595–10601.
- (37) Huang, X.; Li, J.; Zhang, Y.; Mascarenhas, A. *J. Am. Chem. Soc.* **2003**, *125*, 7049–7055.
- (38) Narayan, T. C.; Miyakai, T.; Seki, S.; Dincă, M. *J. Am. Chem. Soc.* **2012**.
- (39) Li, H.; Eddaoudi, M.; O’Keeffe, M.; Yaghi, M. *Nature* **1999**, *402*, 276–279.
- (40) Giannozzi, P.; Baroni, S.; Bonini, N.; Calandra, M.; Car, R.; Cavazzoni, C.; Ceresoli, D.; Chiarotti, G. L.; Cococcioni, M.; Dabo, I.; Dal Corso, A.; de Gironcoli, S.; Fabris, S.; Fratesi, G.; Gebauer, R.; Gerstmann, U.; Gougoussis, C.; Kokalj, A.; Lazzeri, M.; Martin-Samos, L.; Marzari, N.; Mauri, F.; Mazzarello, R.; Paolini, S.; Pasquarello, A.; Paulatto, L.; Sbraccia, C.; Scandolo, S.; Sclauzero, G.; Seitsonen, A. P.; Smogunov, A.; Umari, P.; Wentzcovitch, R. M. *J. Phys. Cond. Mat.* **2009**, *21*, 395502.
- (41) Perdew, J. P.; Chevary, J. A.; Vosko, S. H.; Jackson, K. A.; Pederson, M. R.; Singh, D. J.; Fiolhais, C. *Phys. Rev. B* **1992**, *46*, 6671–6687.

- (42) Perdew, J. P.; Burke, K.; Wang, Y. *Phys. Rev. B* **1996**, *54*, 16533–16539.
- (43) Dal Corso, A. PSLibrary <http://qe-forge.org/gf/project/pslibrary/>.
- (44) Monkhorst, H. J.; Pack, J. D. *Phys. Rev. B* **1976**, *13*, 5188–5192.
- (45) Marzari, N.; Vanderbilt, D.; De Vita, A.; Payne, M. C. *Phys. Rev. Lett.* **1999**, *82*, 3296–3299.
- (46) Rappe, A. K.; Casewit, C. J.; Colwell, K. S.; Goddard, W. A.; Skiff, W. M. *J. Am. Chem. Soc.* **1992**, *114*, 10024–10035.
- (47) Hanwell, M. D.; Curtis, D. E.; Lonie, D. C.; Vandermeersch, T.; Zurek, E.; Hutchison, G. R. *J. Cheminform.* **2012**, *4*, 17.
- (48) Hudson, B. S.; Allis, D. G. *J. Mol. Struct.* **2013**, *1032*, 78–82.
- (49) Phan, A.; Doonan, C. J.; Uribe-Romo, F. J.; Knobler, C. B.; O’Keeffe, M.; Yaghi, O. M. *Acc. Chem. Res.* **2010**, *43*, 58–67.
- (50) Yaghi, O. M.; Choi, E. Conductive organometallic framework, 2010.
- (51) Neofotistou, E.; Malliakas, C. D.; Trikalitis, P. N. *Inorg. Chem.* **2007**, *46*, 8487–8489.
- (52) Feng, P.; Bu, X.; Zheng, N. *Acc. Chem. Res.* **2005**, *38*, 293–303.
- (53) Zhang, Q.; Bu, X.; Zhang, J.; Wu, T.; Feng, P. *J. Am. Chem. Soc.* **2007**, *129*, 8412–8413.
- (54) Zhang, Q.; Liu, Y.; Bu, X.; Wu, T.; Feng, P. *Angew. Chem., Int. Ed.* **2008**, *47*, 113–116.
- (55) Brozek, C. K.; Dincă, M. *J. Am. Chem. Soc.* **2013**, *135*, 12886–12891.